

IN THE BOARD OF COUNTY COMMISSIONERS OF THE STATE OF OREGON
JUN 21 11 05 AM '79

FOR THE COUNTY OF YAMHILL

WILLIAM HATT
COUNTY CLERK

SITTING FOR THE TRANSACTION OF COUNTY BUSINESS DEPUTY

In the Matter of an Ordinance to)
Adopt the Yamhill County Land Divi-)
sion Ordinance, 1979, Repealing) O R D I N A N C E N O . 2 0 5
all previous Subdivision Ordinances)
and declaring an Emergency.)

THE BOARD OF COMMISSIONERS OF Yamhill County, Oregon (the Board), on the 28th day of June, 1979, sat for the transaction of County business, Commissioners Colin Armstrong, Ted Lopuszynski and John P. Macaulay being present.

WHEREAS, pursuant to ORS 215.050 and 197.175, the Board is required to enact a subdivision ordinance designed to implement the Yamhill County Comprehensive Plan and the Statewide Goals of the Land Conservation and Development Commission (LCDC); and

WHEREAS, a task force of the citizen Planning Advisory Committees of the County, at meetings on April 29, 1979, May 8, 1979, and May 15, 1979, and the Planning Commission at public hearings on May 22, 1979, June 12, 1979 and June 15, 1979, reviewed this Land Division Ordinance for compliance with ORS Chapter 92, ORS Chapter 215, LCDC's Goals, and the Yamhill County Comprehensive Plan; and

WHEREAS, the Board held a public hearing on this Ordinance on June 28, 1979, and considered the recommendations of the public, the task force and the Planning Commission; NOW, THEREFORE,

THE BOARD OF COMMISSIONERS FOR YAMHILL COUNTY, OREGON, ORDAINS AS FOLLOWS:

SECTION 1. The Yamhill County Land Division Ordinance No. 205, attached hereto and by this reference made a part hereof, is hereby adopted by the Board.

SECTION 2. Any application filed before and still pending on the effective date of this Ordinance shall be processed under the Ordinance in effect when the application was filed. The provisions of paragraph 18.050 notwithstanding, the attached Yamhill County Land Division Ordinance No. 205 shall not apply to any such pending application.

SECTION 3. This Ordinance being necessary for the health, safety and welfare of the people of Yamhill County, and the Board having declared an emergency to exist, it shall be effective upon the approval

FILED
YAMHILL COUNTY, OREGON

JUL 2 11 25 AM '79

hereof.

APPROVED this 28th day of June, 1979, at McMinnville,
DEPUTY

Oregon.

ATTEST:

YAMHILL COUNTY BOARD OF COMMISSIONERS:

WANDA CATT, County Clerk

by: Patricia A. Mullen
Patricia A. Mullen,
Deputy

(Not available for signature)
Chairman Colin Armstrong

Ted Lopuszynski
Commissioner Ted Lopuszynski

APPROVED AS TO FORM:

Robert S. Willoughby
Robert S. Willoughby
Yamhill County Counsel

John P. Macaulay
Commissioner John P. Macaulay

TABLE OF CONTENTS

		Page
ARTICLE I	INTRODUCTORY PROVISIONS	1
Chapter 1	Title	2
Chapter 2	General Purpose	3
Chapter 3	Definitions and Rules of Construction	5
ARTICLE II	PRELIMINARY PROCEDURE AND DESIGN	14
Chapter 4	Initial Application and Review Procedures	16
Chapter 5	Preliminary Map and Preliminary Plat Requirements	25
Chapter 6	General Design Standards	30
ARTICLE III	SPECIAL PROVISIONS	41
Chapter 7	Minor Partitions, Major Partitions, Subdivisions	43
Chapter 8	Major Partitions, Supplementary Provisions	50
Chapter 9	Subdivisions, Supplementary Provisions	51
ARTICLE IV	FINAL PROCEDURE	53
Chapter 10	Final Application and Review Procedure for Major and Minor Partitions	55
Chapter 11	Final Application and Review Procedure for Subdivisions	63
ARTICLE V	ADMINISTRATION	70
Chapter 12	Administrative Authority	71
Chapter 13	Bonding performance Agreements	75
Chapter 14	Variances	78
Chapter 15	Public Hearings	80
Chapter 16	Appeals	81
Chapter 17	Filing Fees	84
ARTICLE VI	GENERAL PROVISIONS	85
Chapter 18	General Provisions	86

ARTICLE I
INTRODUCTORY PROVISIONS

CHAPTER 1. Title.

1.000 This Ordinance shall be known and may be cited or pleaded as the Yamhill County Land Division Ordinance No. 205, 1979.

CHAPTER 2. General Purpose.

2.000 The general purpose of this Ordinance is to define subdivision, partition and related terms; to prescribe the form and content of subdivision plats and partition maps, the procedures to be followed in their development, and to designate those authorized to give approval; to establish the minimum requirements and standards necessary for efficient, safe, and attractive subdivisions and partitions consistent with the natural resources of the County; and to provide penalties for violations. It is intended that this Ordinance be consistent with ORS, Chapter 92, 197 and 215.

It is further the purpose of this Ordinance:

1. To ensure that land be subdivided or partitioned in a manner which will promote the public health, safety, convenience, and general welfare.
2. To aid in the implementation of the Comprehensive Plan for Yamhill County and any element thereof.
3. To emphasize and conserve the natural resources of the County by providing the means for encouraging orderly development.
4. To minimize, through proper design and layout, the danger to life and property by the hazards of fire, flood, water pollution, soil erosion, and land slippage.
5. To ensure that proper consideration be given for adequate light, air and land capability in the subdivision or partition and the adjoining residential development.
6. To allow lots, parcels, and development sites of sufficient size and appropriate shape and character for the purpose of which they are to be used.

7. To provide for adequate water supply, sewage disposal, storm drainage, and other utilities needed for the public health, safety, convenience and general welfare.
8. To provide an adequate road network, being designed to handle the anticipated usage and to minimize safety hazards and adverse impacts on the neighboring areas and the environment.
9. To ensure that the costs of providing rights-of-way and improvements for vehicular and pedestrian traffic, utilities, and public areas serving new developments be substantially borne by the benefited persons rather than by the people of the County at large.
10. To ensure that local public services will not be adversely effected or over extended by the proposed development, to include: police protection, fire protection, and the adequacy of the local school district to provide the required service.
11. To emphasize the conservation of energy and the use of renewable and indigenous energy resources.

CHAPTER 3. Definitions and Rules of Construction.

3.000 Rules of Construction. For the purposes of this Ordinance, all words, terms and expressions contained herein shall be interpreted in accordance with the following rules of construction, unless the context otherwise requires:

1. The particular controls the general;
2. The word "shall" is mandatory, the word "may" is permissive;
3. The present tense includes the future tense, the singular includes the plural, and the plural includes the singular;
4. The masculine includes the feminine and the feminine includes the masculine;
5. The word person includes a firm, association, organization, partnership, trust, company, or corporation, as well as an individual;
6. Any word, term or phrase, not defined herein shall be construed according to its common, ordinary and accepted meaning.

3.010 Definitions. For the purposes of this Ordinance, the following words and phrases shall mean:

1. Arterial - A street which is used primarily for through traffic, or which by its location will likely be needed for such use in the normal growth of a community or the county.
2. Board - Yamhill County Board of Commissioners.
3. Building Site - That portion of the lot or parcel of land upon which the building and appurtenances are to be placed, or are already existing, including adequate areas for sewage disposal, light, air clearances, proper drainage and appropriate easements.

4. City Owned Sewage Disposal System - A city owned and operated sewer district regulated by the State Department of Environmental Quality.
5. Collector Street - A street other than an arterial which is used primarily for carrying traffic to one or more arterials.
6. Commission - Yamhill County Planning Commission.
7. Commissioners Journal - An index of the orders, resolutions and agreements made by the Board and the minutes of all regular Board meetings as recorded in the records of the Yamhill County Clerk.
8. Community Water Supply System - A domestic water supply source or distribution system which serves more than three single residences or other users for the purpose of supplying water for household uses, but is neither a municipal water supply system nor a public utility water supply system. A community water supply system must be approved by the State Health Division pursuant to ORS Chapter 448.
9. Comprehensive Plan - The Yamhill County Comprehensive Plan, 1974, as defined in Section 3(5) of the Yamhill County Comprehensive Plan, 1974, Ordinance No. 62, 1974, as amended.
10. Control Strip - A strip of land contiguous to a road which land is deeded or dedicated to the County for the purpose of controlling access or providing a buffer between an adjacent land use.
11. County - The County of Yamhill, a political subdivision of the State of Oregon, including its elected and appointed officials delegated responsibility herein.
12. County Road Standards - An order adopted by the Board entitled Standards And Specifications For Road Construction In Yamhill County, Oregon, 1974, as may be amended by the Board.

13. Development Pattern - The dominant parcelization and land use pattern of the area surrounding a particular property.
14. Director - Director of the Yamhill County Department of Planning and Development.
15. Domestic Water Supply Source - Any lake, pond, impounding reservoir, water storage facility, water treatment facility, spring, well, stream, creek, river, marsh, ditch, canal or other body of water from which water is derived for municipal, public utility, community or private water supply system.
16. Drainage, positive - The direction or movement of surface or subsurface water away from an existing or proposed building site, being consistent with the general drainage pattern of the area.
17. Driveway - A private access road designed to provide vehicular access from a street to a building, but not including an easement.
18. Easement - An estate in land owned by another that entitles its holder to a use.
19. Engineer - The department head or other designated staff members of the Yamhill County Road Department.
20. Hearings Officer - A person authorized by the Board to act in place of the Commission.
21. Land Development Review Committee (LDRC) - A committee established to act in a technical review capacity for the Commission or Hearings Officer on all major partitions and minor partitions; and on subdivisions when all grievances (if any) can be reconciled at or prior to the LDRC meeting. The LDRC shall consist of the following members or their duly authorized representative(s):

- A. Director, Department of Planning and Development,
who shall serve as Chairman.
 - B. Engineer, Road Department.
 - C. Sanitarian, Health Department.
 - D. Chairman of the Board of Directors, Yamhill County
Soil and Water Conservation District.
 - E. Superintendent of the appropriate Yamhill County
Public School District.
 - F. Fire Chief of the appropriate Yamhill County
Rural Fire District.
 - G. Official of the appropriate water district.
 - H. A representative from the appropriate recreational
district.
 - I. The local Planning Advisory Chairman or his designate.
 - J. Such other person as the Director may request to attend.
22. Lot - A unit of land that is created by a subdivision or
partition of land.
23. Lot, corner - A lot abutting on two or more streets other
than an alley, at their intersection. A lot abutting on
a curved street or streets shall be considered a corner
lot if straight lines drawn from the foremost points of
the side lot lines to the foremost point of the lot meet
at an interior angle of less than 135 degrees.
24. Lot, double frontage - A lot abutting on two streets other
than an alley and other than a corner lot.
25. Lot, flag - A lot which takes access on a street, and
has the main body of the lot away from the street, and
which has less than 100 feet of street frontage, and of
which the base of the flag is primarily for access purposes.
26. Lot, interior - A lot other than a corner lot.

27. Lot, reversed frontage - A lot on which the frontage is at right angles or approximately right angles (interior angle less than 135 degrees) to the general street pattern in the area. A reversed frontage lot may also be a corner lot, an interior lot or a double frontage lot.
28. Lot area - The total horizontal area within the lot lines of a lot, exclusive of streets and easements of access to other property.
29. Lot frontage - The front of a lot shall be construed to be the portion nearest the street. For the purposes of determining yard requirements on corner lots and through lots, all sides of a lot adjacent to a street other than an alley shall be considered frontage.
30. Lot line - Is the boundry of a lot.
31. Lot line, front - Is the lot line or lines common to the lot and a street other than an alley, and in the case of a corner lot, the shortest lot line along a street other than an alley.
32. Lot line, rear - Is the lot line or lines opposite and most distant from the front lot line. In the case of an irregular, triangular or other shaped lot, a line ten (10) feet in length within the lot parallel to and at a maximum distance from the front lot line.
33. Lot line, side - Is any lot line or lines not a front or rear lot line. An interior side lot line is a lot line common to more than one lot or to the lot and an alley; an exterior side lot line is a lot line common to the lot and a street other than an alley.

34. Lot measurements -
- A. Depth of a lot shall be considered to be the distance between the midpoints of straight lines connecting the foremost points of the side lot lines in front and the rearmost points of the side lot lines in the rear.
 - B. Width of a lot shall be considered to be the average distance between straight lines connecting front and rear lot lines at each side of the lot.
35. Map - A final diagram or drawing containing the boundary descriptions, location, specifications, dedications, provisions and information concerning a major or minor partition.
36. Map, preliminary - The preliminary major or minor partition diagram or drawing.
37. Non-Residential - Excludes the use of permanent or temporary living accommodations authorized by the Director and Sanitarian.
38. Owner - All persons having right title or interest in a parcel. For the purpose of this Ordinance, owner shall also refer to the owner's authorized agent except when the owner's signature is required.
39. Parcel - Synonymous with "lot."
40. Partition - An act of partitioning land or an area or tract of land partitioned as defined in this Section.
41. Partition, Major - A partition which includes the creation of a road or street.
42. Partition, Minor - A partition which does not include the creation of a road or street, but may include the widening of an existing road or street.

43. Partition Land - To divide an area or tract of land into two or three parcels within a calendar year when such area or tract of land exists as a unit or contiguous units of land under single ownership at the beginning of such year.
- A. "Partition land" does not include divisions of land resulting from the creation of cemetery lots; and "partition land" does not include any adjustment of a lot line by the relocation of a common boundary where an additional parcel is not created and where the existing parcel reduced in size by the adjustment is not reduced below the minimum lot size established by any applicable zoning ordinance.
- B. "Partition land" does not include the sale of a lot in a recorded subdivision, even though the lot may have been acquired with other contiguous lots or property by a single owner.
- C. Partition land does not include the sale of an interest in timber.
44. Planned Unit Development - Is any area of land which contains or will contain two (2) or more principal buildings developed under single ownership or control, the development of which is unique and of a substantially different character than that of surrounding areas, and shall be based on a plan which allows for flexibility of design not available under the normal zoning district or subdivision requirements. Any area of land developed on this basis shall be included in the Planned Unit Development (PUD) zoning district of the Yamhill County Zoning Ordinance, and any area of land included in said District shall be so developed.

45. Plat - A final diagram, drawing or replat containing all of the descriptions, locations, specifications, dedications, provisions and information concerning a subdivision as required herein and consistent with ORS 92.
46. Plat, preliminary - The preliminary subdivision diagram, drawing, replat which meets the requirements as specified within this Ordinance.
47. Publicly or Privately Owned Sewer Disposal System - A sewer district regulated by the State Department of Environmental Quality.
48. Public Areas - Those places within the unincorporated area of Yamhill County that are dedicated, designated or in use of the general public. To include rights-of-way, parks, schools, and other such facilities.
49. Road or Street - A public or private way that is created to provide ingress or egress for persons to one or more lots, parcels, areas or tracts of land.
50. Rural Development Areas - Those lands designated Agriculture & Forestry Small Holding (AFSH), Very Low Density Residential (VLDR), and Low Density Residential (LDR) on the Comprehensive Plan.
51. Sale (Sell) - Includes every disposition or transfer of land in a subdivision or partition or an interest or estate therein. Sale shall also include the exchange of property. Sale shall not apply to a conveyance of interest in timber.
52. Sanitarian - Yamhill County Sanitarian.

53. Subdivide Land - To divide an area or tract of land into four or more lots within a calendar year when such area or tract of land exists as a unit or contiguous units of land under a single ownership at the beginning of such year.
54. Subdivision - An act of subdividing land or an area or a tract of land subdivided as defined in this s Section.
55. Urban Growth Boundary (UGB) - A line jointly adopted by the city and county that encircles the city and separates rural and urbanizable land.
56. Zoning Ordinance - The Yamhill County Zoning Ordinance, Ordinance No. 83, 1976 as may be amended. The Zoning Ordinance includes the Official Zoning Map together with all explanatory matter thereon and any amendments thereto adopted as part of said ordinance.

ARTICLE II
PRELIMINARY PROCEDURE AND DESIGN

ARTICLE 2

PRELIMINARY PROCEDURE

This Article is divided into three chapters and prescribes the "preliminary procedure" for creating a partition or a subdivision.

1. INITIAL APPLICATION AND REVIEW PROCEDURES - Chapter 4, provides an application and review procedure, designed to achieve maximum coordination between the owner and the Director with the least amount of delay or confusion.
2. PRELIMINARY PLAT AND PRELIMINARY MAP REQUIREMENTS - Chapter 5, provides the format for drawing the preliminary plat or preliminary map which must be submitted together with the initial application.
3. GENERAL DESIGN STANDARDS - Chapter 6, provides the minimum standards necessary for design of a partition or a subdivision.

CHAPTER 4. Initial Application and Review Procedures.

4.000 Pre-Application Conference - Prior to submitting an application and preliminary plat of a subdivision or preliminary map of a partition, the owner shall confer with the Director and discuss the initial components of the proposed division. The Director shall provide information regarding procedure, zoning and subdivision requirements, elements of the Comprehensive Plan and other information having a direct influence upon the proposed development.

The Director shall provide the owner with a written summary of the review session when:

1. The applicants proposal does not comply with the intent of the Comprehensive Plan, Zoning Ordinance or other ordinances that may be adopted that would be in conflict with the application.
2. The application requires the submission of variance requests, other public planning actions, or additional information of a technical nature as provided by this ordinance.
3. Requested by the applicant.

4.010 Submission of Initial Application - Formal review of a proposed subdivision or partition will not commence until an application and preliminary plat or preliminary map is submitted to the Director in substantial conformity to the provisions of this Ordinance, and when necessary, that the appropriate variances have been requested and submitted pursuant to this Ordinance.

4.020 Application - Following the Pre-Application Conference, the Owner proposing the subdivision or partition shall make an application in writing on a form prescribed by the Director. Each application shall be accompanied by the appropriate filing fee and five (5) copies of the preliminary plat or preliminary map. The preliminary plat or preliminary map shall meet the specifications as set forth in this Ordinance. The

Director may require the owner to submit additional copies of the preliminary plat or preliminary map when necessary for referrals or public hearings.

4.030 Field Inspection - The Director may make a field inspection of the parcel being subdivided or partitioned to determine whether the proposed division of land is consistent with those design standards and general requirements set forth in this Ordinance, and to determine whether supplementary information is needed.

4.040 Referral - Upon receipt of an acceptable application and preliminary plat or preliminary map, the Director shall refer such to:

1. County Engineer
2. County Sanitarian
3. Special Districts
4. Municipality (if within a six mile radius)
5. Other persons or agencies deemed appropriate for comment of their preliminary investigations.

Each county office mentioned above is charged with the duty of making a preliminary investigation to determine compliance to the applicable County and State requirements.

The Director may assume that the proposed subdivision or partition does not conflict with the requirements or interests of any department, person or agency receiving a referral unless written comment regarding such is submitted to the Director within fifteen days from the date of the referral.

If the Director determines that the application and preliminary plat or preliminary map are not in substantial conformity to the provisions of this Ordinance at such time that referrals are returned to the Director, then the Director shall return the application and preliminary plat or preliminary map to the owner together with a finding which indicates the general deficiencies. No further review of the subdivision or partition application shall be made until an acceptable application and preliminary plat or preliminary map are submitted to the Director by the owner pursuant to Section 4.010 of this Ordinance.

4.050 Notice of Land Development Review Committee (LDRC) Meeting -

Upon satisfactory completion of Section 4.040, notice shall be sent as follows:

1. Partitions, Major and Minor -

- A. Notice shall be sent to the owner of the time and date set for the LDRC meeting which shall be at least 15 days after the date of referral pursuant to Section 4.040 of this Ordinance.

2. Subdivisions -

- A. Notice of the intent to subdivide shall be sent by mail to the owner, Planning Advisory Committee whose district includes the property intended to be subdivided, and all property owners within 250 feet of the property which is subject of the application. Notice of the intent to subdivide shall also be given by publication in a newspaper of general circulation in the area of the subject property.

- B. The notice of the intent to subdivide shall clearly indicate the following:

- (1) Name of the owner/subdivider, description of the parcel or parcels identified by Township, Range, Section, tax lot number and address if any. The description shall also indicate the general vicinity of the property proposed to be subdivided, and a general description of the request.
- (2) Fifteen (15) days is provided from the date of mailing in which to submit statements in support or opposition to the request to the Yamhill County

Department of Planning and Development. All statements in support or opposition shall be in writing and shall contain:

- a. proponents or opponents name, address and telephone numbers,
 - b. how the proponent or opponent is specially, personally or adversely affected by the application, or that the proponent or opponent is a property owner within 250 feet of the property under review, and
 - c. a brief statement of the reasons for support or opposition.
 - d. notwithstanding subsection b above, statements may be received from an expert witness when such statement is submitted together with, or in conjunction with an opponent's or proponent's statement.
- (3) The time and date of the LDRC meeting which shall be set as soon as possible.
- (4) A statement to the effect that failure of the proponent, opponent or their authorized agent to either submit a statement in support or opposition in the form described in Subsection 2, paragraph B above, or to attend the LDRC meeting shall constitute a waiver of said proponent's or opponent's objections or grievances.

C. In lieu of paragraphs A and B of this Subsection, the owner may request a public hearing before the Commission (or Hearings Officer if one is available) pursuant to Chapter 15 of this Ordinance. Nothing in this Section shall be construed to prevent the LDRC from meeting and presenting a report to the Commission on any matter subject to the provisions of this Ordinance.

4.060 Notice of Decision - Upon completion of the preliminary review requirements, the Director (or in the case of a public hearing, the Commission or Hearings Officer) shall grant, deny, or in appropriate cases attach conditions to the preliminary plat or preliminary map. The Director shall promptly notify the Board, the owner, referral agencies, those submitting statements in support or opposition, those present at the review session and those requesting information in writing of such decisions. Notification of the decision shall include findings which ascertain that:

1. The proper procedures were followed;
2. The relevant factors were considered by the County; and
3. There was reliable, probative and substantial evidence to support the decision of the County. Notification of the decision shall also include a notification of the right of appeal.


4.070 Effective Date - Unless the action by the Director (or in the case of a public hearing, the Commission or Hearings Officer) is appealed or the Board elects to hold a hearing on the preliminary plat or preliminary map, the Director's (Commission's or Hearings Officer's) action shall become final thirty (30) days after the date of the written Notice of Decision.

4.080 Effect of Approval - Following approval of a preliminary map or a preliminary plat, the owner may proceed with final preparation of the partition map or subdivision plat and the necessary improvements pursuant to the provisions of this Ordinance.


Approval of the preliminary map or preliminary plat shall not constitute final acceptance of the final map or plat for recording; however, approval by the County of such preliminary map or preliminary plat shall be binding upon the owner and the County for the purposes of the preparation of the final map or plat.

4.090 Expiration of Preliminary Approval - If the owner does not within one (1) year submit the final subdivision application, or within six (6) months submit the final partition application (in complete form), the preliminary approval shall be null and void and shall no longer be binding upon the County.


PRELIMINARY PROCEDURE
MINOR PARTITION



PRELIMINARY PROCEDURE
MAJOR PARTITION



PRELIMINARY PROCEDURE SUBDIVISIONS



CHAPTER 5. Preliminary Map or Plat Requirements.

5.000 The following shall be required on the face of a Preliminary Map of a Minor or Major Partition:

1. The Preliminary Map shall be drawn on high quality reproducible paper 8 1/2 x 14 inches in size at a scale of no less than 1" = 400' and shall indicate the following:
 - A. Date, North Point and scale of the drawing.
 - B. Name, address and telephone number of the record owner(s), owner's representative, and designer(s) of the proposed land division and the name of the Engineer(s) or the Surveyor(s) and the date of the survey and file number, if any.
 - C. Proof of record ownership of the tract and the representatives authorization.
 - D. Description: The location of the property by tax account number, Township, Range, the most recent recorded deed instrument number and the zoning district designation.
 - E. Appropriate identification of the drawing as a Preliminary Map.
 - F. Lot identification: All lots shall be numbered in consecutive order and shall indicate lot size in acreage or square feet.
 - G. The estimated dimensions and boundaries of all lots to be created, together with the designation of any subdivision, public roadway, right-of-way or easement of record.

- H. Contour lines at intervals of not less than five (5) feet for partitions having lots which average one (1) acre in size or less. Two (2) foot contour intervals may be required when greater topographical detail is necessary to determine such things including but not limited to: a. Drainage; b. Ground movement; c. Unique topographical features.
 - I. The location of all existing structures and proposed structures on the area to be partitioned that are to be created or remain in place.
 - J. All easements of record to/or across the land to be divided together with their dimension and stated purpose.
 - K. A vicinity sketch showing the location of the subject property, its location in relation to adjoining property, the owners thereof, major roads, topographical features (i.e. rivers, streams, mountains) and cities.
 - L. Proposed means and location of sewerage disposal and water supply source.
 - M. Such additional information as the Director deems necessary for the evaluation of the application.
2. The following shall be required on the Preliminary Map of a Major Partition in addition to the preceding requirements:
- A. Contour lines at intervals of not less than five (5) feet for the entire tract to be partitioned.
 - B. Existing and proposed drainage patterns which show the direction and volume of surface water runoff in sufficient detail to determine the effect of the drainage.
 - C. General road layout and approximate grades.

- D. A preliminary plan and profile of the proposed roadway at a scale of not less than 1" = 100' in accordance with The Standards and Specifications for Road Construction in Yambill County, 1975.

5.010 The following shall be required on the Preliminary Plat of a Subdivision.

1. The Preliminary Plat shall be drawn on high quality reproducible paper 18 X 24 inches in size at a scale of not less than 1" = 200' and shall indicate the following:
 - A. Date, North Point and scale.
 - B. Name, address and telephone number of the record owner(s), owner's representative, and designer(s) of the proposed subdivision and the name of the Engineer(s) or the Surveyor(s) and the date of survey and file number, if any.
 - C. Proof of record ownership of the tract and the representatives authorization.
 - D. Description: The location of the property by tax account number, Township, Range, Section, the most recent deeded instrument number and zoning district designation.
 - E. Appropriate identification of the drawing as a preliminary plat.
 - F. Proposed name for subdivisions, except for additions to existing subdivisions, no subdivision name shall be used which will duplicate or be confused with names of existing subdivisions.
 - G. Proposed street names. Except for extensions of existing streets, no street name shall be used which will duplicate or be confused with the names of existing streets.

- H. Block identification: All blocks shall be numbered or lettered in consecutive order.
- I. Lot identification: All lots shall be numbered in consecutive order and shall indicate lot size in acreage or square feet.
- J. The estimated outer boundaries of all tracts of contiguous land in the same ownership from which the subdivided parcels are created.
- K. The estimated dimensions and boundaries of all lots and parcels to be created, together with the designation of any adjoining subdivision, public roadway, right-of-way or easement of record.
- L. Contour lines at intervals of not less than five (5) feet. Two (2) foot contour intervals may be required when greater topographical detail is necessary to determine such things including but not limited to:
 - a. Drainage; b. Ground movement; c. Unique topographical features.
- M. The location of all existing and proposed structures on the area to be subdivided that are to be created or remain in place.
- N. Existing and proposed drainage patterns which show the direction and volume of surface water flow in sufficient detail to determine the effect of the drainage.
- O. General street layout and approximate street grades.
- P. All recorded easements to and/or across the land to be divided, together with their dimensions and stated purpose.
- Q. A vicinity sketch showing the location of the subject property in relation to adjoining property boundaries

within 300 to 800 feet, major roads, topographical features (i.e. rivers, streams, mountains) and cities.

- R. Proposed means and location of sewage disposal and water supply.
- S. Proposed homeowner association by-laws, covenants or deed restrictions affecting the proposed preliminary plat.
- T. Such additional information as the Director deems necessary.

CHAPTER 6. General Design Standards.

6.000. General Requirement -

1. Conformity to the Comprehensive Plan, Official Map, Zoning Ordinance and Other Ordinances or Factors - The subdivision or partition shall conform to and be in harmony with the County Comprehensive Plan, the development pattern, the Zoning Ordinance and any other ordinance legally adopted or amended.
2. Conformity to State Requirements - The subdivision or partition shall conform to the requirements as set forth in the Oregon Revised Statutes (O.R.S.), Chapters 92, 197 and 215.

6.010 Street Design -

1. Relation to the Adjoining Street System - A subdivision or partition shall provide for the continuation of the principal street(s) existing in the adjoining area, or of their proper projection when adjoining property is not developed, and such street(s) shall be of a width and standard of not less than the minimum requirements for streets as set forth in this Ordinance and the Standards And Specifications For Road Construction in Yamhill County, Oregon.
2. Where the preliminary plat or preliminary map submitted covers only a part of the subdivider's or partitioner's tract, or when there are indications that contiguous lots, parcels or units of land will eventually be subdivided or partitioned, then the owner may be required to demonstrate that the subdivision

or partition can substantially conform and be in harmony with the eventual orderly development of the entire tract or contiguous lands. The Director may require the owner to submit a drawing (at the time of initial application) of a general or prospective future street system and lot layout of the entire tract or contiguous units of land.

3. Where a tract is divided into lots of 20,000 square feet or more, the Director may require an arrangement of lots and streets such as to permit a later redivision in conformity to the requirements contained in this Ordinance. The location of lot lines and other details of the layout shall be such that further division of the parcels may readily take place without interfering with the orderly development of streets. The Director may restrict the placement or location of structures, easements, facilities or other uses which may cause an infringement upon the use or development and improvement of an existing or anticipated street or roadway.
4. Except as provided in Section 6.030, Subsection 7 (Private easements/Driveways) of this Ordinance, no partition or subdivision or dedication of any area shall be approved by the Director unless the streets shown therein are connected to an existing street which the County Engineer finds to be adequate to accommodate the additional use generated by the development.
5. Where a subdivision or partition contains or abuts an existing or proposed arterial street, railroad right-of-way or limited access thoroughfare, the Director may require

additional design standards which are deemed necessary for adequate protection and buffering of residential, commercial or industrial property, which may include, but is not limited to:

- A. frontage streets,
- B. limited access locations,
- C. reverse frontage lots,
- D. increase lot depth requirement on those lots abutting the arterial, railroad right-of-way or limited access thoroughfare,
- E. planting easements, and
- F. sight obscuring screen planting or fencing.

6. Street and cul-de-sac widths and improvements.

- A. The creation of any road and the standard street section requirements shall conform to the County Road Standards and this Ordinance, however when the creation of any public road is located within the Urban Growth Boundary of a city having more restrictive road requirements, then the city road requirements shall apply.
- B. Except as provided in paragraph C below, all streets designed for public dedication shall have a right-of-way width of not less than 60 feet. Additional right-of-way may be required in order to properly accommodate all road cut and fill slopes and the placement and installation of utilities.

- C. Cul-de-sac streets which serve as access to parcels averaging 20,000 square feet in area or less shall not exceed 500 feet in length, and shall otherwise not exceed 1500 feet in length. Each cul-de-sac must be terminated by a turnaround right-of-way of not less than one hundred (100) feet in diameter. The minimum right-of-way for cul-de-sac streets shall be 50 feet.
- D. Temporary Deadend Streets. Where a street is designed to remain only temporarily as a deadend street, an adequate (all weather) temporary turning area and drainage system shall be provided at the deadend thereof, to remain and be available for public use so long as the deadend condition exists. Construction of the temporary turnaround and drainage system shall meet with the approval of the County Engineer.
- E. Half-streets proposed along a subdivision boundary or within any part of a subdivision or partition shall not be approved.
- F. Street Grades may be permitted up to 15 percent provided they do not exceed 200 feet in length, whereby they must be reduced to 10 percent or less for a minimum length of 200 feet. The overall maximum sustained grade shall not exceed 10 percent.

7. Private Easements/Driveways

- A. A private easement may be established in accordance with this Ordinance provided it is the only reasonable method by which a lot may be provided with access. If the existing lot contains sufficient acreage so that (4) or more parcels meeting the lot size minimums established by the County Zoning Ordinance could be created, or if the applicant owns contiguous parcels which contain sufficient acreage to divide the property into (4) or more parcels, and it is possible to provide access to each lot by creating a public road then this exception shall not apply.
- B. The minimum right-of-way for a private easement shall not be less than 30 feet.
- C. No more than three parcels may be served by a private easement.
- D. Private driveways shall be constructed in accordance with specifications determined by the Yamhill County Road Department Head, or his designate.
- E. Minimum Standards for Private Easement Construction are as follows:
- | | |
|---|------------------|
| (1) Minimum Travel Surface Width | 12 feet |
| (2) Minimum Vertical Clearance | 14 feet |
| (3) Minimum Horizontal Clearance | 16 feet |
| (4) Maximum Intermittent Grade | 15% for 200 feet |
| (5) Maximum Sustained Grade | 10% |
| (6) (Road curve standard) | |
| (7) Culverts, Bridges and other drainage structures | |
- shall be placed so as to encourage drainage in established drainage ways.

- (8) All private roadways and easements shall be constructed in accordance with the Standards and Specifications for Road Construction in Yamhill County, 1975, or to a standard determined by the Yamhill County Road Department Head or his designate.
- (9) Those roads longer than 400 feet in length must provide turnouts at least every 800 feet or less as required by the County Road Department. Turnouts must provide 10 feet of additional road width for a minimum distance of 30 feet in addition those roads which exceed 400 feet in length, having only one entrance onto the County Road system shall provide one or more turnarounds. Turnarounds should be circular with at least a 30 foot radius wherever possible, but may be modified by the County Engineer where it is found that:
- a. The size and design of the turnaround is sufficient to allow at least a 1000 gallon pumper fire truck to turn around without backing up more than once.
 - b. The perimeter of the turnaround is properly marked to allow visual guidance when a vehicle is turning around or backing up.
- (10) Construction of turnouts and turnarounds shall be made to the same standard as required for private easement construction.
- (11) Additional road construction improvements may be required in areas exhibiting poor soil stability,

drainage or other abnormal conditions including but not limited to abnormal traffic volumes or heavy truck traffic.

- E. It shall be the responsibility of the benefited property owners to maintain the private easement or driveway established in accordance with this Ordinance. The Director may require the establishment of a road maintenance association, covenant or other similar requirement for the perpetual maintenance of such road.

6.020 Access to Parcels.

1. There shall be direct legal access to and abutting on every lot or parcel.
2. The land provided for public roadways and easements or easements of a public or private utility system shall be clearly defined on the preliminary plat or preliminary map.

6.030 Lots.

1. Lot Shape. Lots should form or approximate conventional shapes, and shall otherwise be consistent with the Zoning Ordinance.
2. Lot Access. Every lot shall abut and have adequate access to a public street and shall have a road frontage of not less than fifty (50) feet, except as provided below:
 - A. A lot on the radius of a curved street or facing the circular end of a cul-de-sac shall have frontage of not less than thirty (30) feet upon a street, measured on the arc of the right-of-way.

- B. Minimum access widths for flag lots shall be thirty (30) feet, except that a greater width may be required if it is possible that more than two parcels could be served from such access as their only means of legal access.
- C. No more than three parcels may be served by a private easement which has a minimum width of thirty (30) feet. Roads which are to serve as access to four or more parcels shall be constructed to the specifications required by the County Road Standards.
3. Flag Lots and Double Frontage Lots. Flag lots shall not be permitted except where, in the judgement of the Director, the parcel shape, topography, or other factors makes such lot unavoidable. Lots which have street frontage along two (2) opposite boundaries (double frontage lots) may be permitted if the boundary along one of the streets is established as the rear lot line.
4. Lot Bordering a Water Body or Stream Course. In creating parcels of two (2) acres or less in a partition or subdivision, the minimum lot area shall not include those lands, tracts, areas, or portions of a lot located below the mean high water elevation of a lake, river, stream or other water body.
5. Lot Sidelines. As far as practical, lot side lines shall run at right angles to the street upon which the lots face, except that on curved or cul-de-sac streets, they shall be radial to the curve. The Director may vary this requirement when it is found that existing topography, providing for solar orientation or other factors, make such a requirement impractical.

6. Lot Drainage. Lots shall be laid out so as to provide positive drainage away from all buildings. Individual lot drainage shall be coordinated with the general stream drainage pattern for the area. Drainage shall be designed so as to avoid unnecessary concentration of storm drainage water from each lot to other lots or parcels. Drainage systems shall be designed and constructed to the specifications that may be hereafter adopted by Board Order and recorded in the Commissioners Journal.

6.040 Blocks.

1. In a subdivision or partition having lots which average one (1) acre or less, the blocks shall not exceed 1,000 feet in length, except blocks adjacent to arterial or collector streets, railroad right-of-way or limited access thoroughfare.
2. Pedestrian walkways. The subdivider may be required to dedicate and improve a ten (10) foot pedestrian walkways across blocks over six hundred (600) feet in length and/or to provide access to schools, parks or other public areas. Pedestrian walkways shall be surfaced in a manner appropriate to the level of development.

6.050 Utility Easements. - Easements for sewers, drainage, water mains, public utility installation, including overhead or underground systems, and other like public purposes shall be placed in road right-of-ways, walkways and planting strips subject to the approval by the County Engineer, or shall otherwise be dedicated, reserved or granted by the subdivider in widths not less than fifteen (15) feet centering along or abutting side or rear lot lines where deemed necessary.

6.060 Watercourses - Where a partition or subdivision is traversed or bounded by a watercourse, drainage way, wasteway, channel or stream, the Director may require a stream water easement or drainage right-of-way conforming substantially to the line of such watercourse, drainage way, wasteway, channel, or stream, and of such width as to allow for construction, maintenance, and control as will be adequate for the purpose as required by the appropriate agency.

6.070 Lands Subject to Hazardous Conditions - Lands which the Director finds to be unsuitable for development due to flooding, inadequate drainage, steep slopes, rock formations, earthquake activity, landmass instability, pollutants or other factors or conditions likely to be harmful to the safety, and general health of future residents or the general public, and which the Director considers inappropriate for development, shall not be developed for building purposes and may be used for open space unless adequate methods for overcoming these conditions are submitted and approved by all appropriate agencies.

6.080 Land for Public Purposes - If the County has an interest in acquiring a portion of a proposed subdivision for a public purpose, or if the County has been advised of such interest by a school district or other public agency, and there is reasonable assurance that steps will be taken to acquire the land, then the Director may require that those portions of the subdivision or partition be reserved for public acquisition, for a period not to exceed one year, at a cost not to exceed the value of the land prior to subdivision.

6.090 Water Supply - All lots within a partition or subdivision shall have an adequate quantity and quality of water to support the proposed use of the land.

1. Where a water supply from a community utility system is available, the owner shall provide the subdivision or partition with a complete water main system connected to the community system.
2. Where a water supply from a community utility system is not available, the owner may be required to provide adequate test well(s), the number and locations of which shall be determined by the Director, and Watermaster having jurisdiction.

6.100 Sewage Disposal Requirement -

1. Sewage Disposal - All lots within a partition or subdivision to be used for residential purposes shall have either an approved sub-surface septic site evaluation or be connected to a sewer treatment facility approved by the State Department of Environmental Quality.
2. Site Evaluation - On any parcel to be created by subdivision or partition for residential purposes, which is not served by a public sewer system, the owner shall provide the Director with an approved septic site evaluation or approval of an alternative sewer disposal facility from the County Sanitarian or the State of Oregon Department of Environmental Quality for each lot to be created for residential purposes. An approved site evaluation or a permit issued by the State Department of Environmental Quality for an alternate sewer disposal facility for each lot intended for residential purposes shall be submitted to the Director before preliminary approval may be granted.

ARTICLE III
SPECIAL PROVISIONS

ARTICLE 3

SPECIAL PROVISIONS

This article is divided into three chapters and prescribes additional requirements and supplementary provisions that may be required prior to submission of a final plat or map.

1. Chapter 7 - Provides sales requirements, dedication of right-of-way, surveying requirements and standards of acceptability. Details requirements for water supply to all proposed parcels and outlines sewage requirements.
2. Chapter 8 - Stipulates supplementary provisions for major partitions only.
3. Chapter 9 - Stipulates supplementary provisions for subdivisions and pertains to street improvements and subdivision of Agricultural Land; and Park requirements for all Land Divisions.

CHAPTER 7. Minor Partitions, Major Partitions, Subdivisions - The following provisions shall apply to all land divisions and may be required by the Director for submission with the final plat or map in accordance with the provision of this Ordinance and ORS 92.

7.000 Sales Requirement - No person shall sell any lot in any subdivision, or partition until the final subdivision plat or partition map and all pertinent material have been approved and recorded in accordance with the provisions of this Ordinance and O.R.S. Chapter 92.

7.010 Planned Unit Development - The Commission or Hearings Officer may modify all or part of the design standards identified in Chapters 6 and 7 of this Ordinance when a Planned Unit Development is utilized, provided:

1. The PUD conforms to the requirements as specified in the Yamhill County Zoning Ordinance.
2. All roads to be dedicated to the County shall conform to the Standards And Specifications For Road Construction In Yamhill County, Oregon.
3. All privately maintained roads shall be designed to accommodate emergency vehicular traffic, must be approved by the County Engineer and the Planning Commission, and shall not be constructed to a standard less than those required for private easements, Section 6.010, Subsection 7 of this Ordinance.
4. The PUD shall conform to the general purpose of this Ordinance and shall be governed by these standards and procedures.

7.020 Road Widening and Dedication of Right-of-Way - Road widening of substandard width roads will be encouraged in all areas, zones and plan designations where deemed necessary to provide for an adequate means of access, transportation, walkways, maintenance and the placement of utilities. Mandatory widening of substandard roads and/or the dedication

of right-of-way or an agreement to dedicate additional right-of-way shall be required in any of the following circumstances:

1. If the road is located in or bounds an area designated on the Yamhill County Comprehensive Plan, 1974, for any use other than "agriculture large holding" or "forestry;" or
2. If the road is shown on the Comprehensive Plan referred to in subsection 1 above or any other future plan dealing with the classification or projection of roads duly adopted by the Board, and the road is designated thereon as a major, secondary, arterial or collector status; or
3. If a subdivision or partition is being proposed, in which case the widening shall be required only along those sides of the existing road bounding the lots or parcels being created; or
4. If the Engineer, on inspection of the proposed subdivision or partition, deems that the public safety requires such widening or that additional right-of-way is necessary to provide for adequate drainage or the installation of utilities anticipated by development of the subdivision or partition.

In any of the foregoing circumstances, the widening shall be sufficient to bring a full road up to a minimum right-of-way width of sixty (60) feet, or a half road up to a minimum right-of-way width of thirty (30) feet.

7.030 Surveying Requirements and Standards

1. The surveying requirements and standards, or evidence of a survey, described in this Section shall apply to:
 - A. All subdivisions and major partitions.
 - B. All roadways within a subdivision or partition.
 - C. All lots being 10 acres or less within a minor partition upon requirement of the Director.

2. The survey of the subdivision (or Partition) shall be of such accuracy that the error of closure shall not exceed one foot in 4,000 feet.
3. The survey and plat of the subdivision or the map of the partition, (when survey is required) shall be made by a land surveyor who is registered with the State of Oregon.
4. The plat of the subdivision or the map of the partition shall be of such scale that all survey and mathematical information, and all other details may be clearly and legibly shown thereon. Each lot shall be numbered and each block shall be lettered or numbered. The lengths of all boundaries of each lot shall be shown. Each street shall be named.
5. The location and description of all monuments shall be carefully recorded upon all plats or maps and the proper course and distances of all boundary lines shall be shown.
6. The initial point of all subdivision plats or partition maps shall be marked with a monument made of galvanized iron pipe, being not less than two inches in diameter and three feet long. The monument shall be driven six inches below the surface of the ground. The location of the monument shall be with reference to some known corner established by the United States survey.
7. The intersections of all streets and roads and all points on the exterior boundary where the boundary line changes direction, shall be marked with monuments either of galvanized iron pipe, or iron or steel rods. If galvanized iron pipe is used, it shall not be less than one inch in diameter and 30 inches long, and if iron or steel rods are used they shall not be less than five-eighths of an inch in least dimension and 30 inches long.

8. All lot corners except lot corners of cemetery lots shall be marked with monuments of either galvanized iron pipe not less than one-half inch in diameter or iron or steel rods not less than one-half inch in least dimension and two feet long.
9. Points shall be plainly and permanently marked upon monuments so that measurements may be taken to them to within one-tenth of a foot.
10. All monuments for the exterior and interior boundaries of a subdivision or partition shall be marked and such monuments shall be referenced on the plat of the subdivision or map of the partition before the plat of the subdivision or map of the partition is offered for recording.

7.040 Water Supply-Improvements - No final plat of a subdivision or map of a partition shall be approved unless the Director and Engineer have received and accepted:

1. A certification by a municipal, public utility or community water supply system, subject to the regulation by the Public Utility Commissioners of Oregon, that water will be provided to the parcel line of each and every parcel depicted in the final plat or map; or
2. A bond, contract or other assurance by the subdivider or partitioner to the County that a domestic water supply system will be installed on behalf of the subdivider or partitioner to the parcel line of each and every parcel depicted on the final plat or map; and the amount of any such bond, contract or other assurance by the subdivider or partitioner shall be determined by a registered professional engineer, subject to any change in such amount as determined necessary by the County; or

3. A water well report filed with the State of Oregon Water Resources Department for each well provided within a subdivision or partition. In addition, the location of such wells and an appropriate disclosure shall be placed on the face of the final plat or map; or
4. In lieu of Subsections (1), (2) and (3) of this Section, when a municipal, public utility, community water supply or private well system is not available, then a statement must be placed on the final plat or map which states:

No municipal, public utility, community water supply or private well system will be provided to the purchaser of those lots noted hereon.

7.050 Sewer Disposal - Improvements - No final plat of a subdivision or map of a partition shall be approved unless the Director and Engineer have received and accepted:

1. A certification by a city-owned, sewage-disposal system or by the owner of a privately owned sewage-disposal system that is subject to regulation by the State Department of Environmental Quality, that a sewage-disposal system will be provided to the parcel line of each and every parcel depicted in the final plat or map; or

2. Certification by the County Sanitarian that an approved subsurface sewage disposal site has been located on the proposed parcel to the specifications prescribed by the State Department of Environmental Quality. Each proposed lot 2 1/2 acres in size or less which is to be served by subsurface sewage disposal systems shall reflect the approved area by survey on the final plat or map along with a statement that reads:

Septic tank drainfields have been approved for those areas noted hereon. The placement of a drainfield shall require approval and permit by the County Sanitarian; or

3. A bond, contract or other assurance by the subdivider or partitioner to the County that a sewage-disposal system, septic tank drainfield or surveyed drainfield area will be installed or provided by or on behalf of the subdivider or partitioner for each and every parcel depicted on the final plat or map; and the amount of such bond, contract or other assurance shall be determined by a registered professional engineer, subject to any change in such amount as the County considers necessary; or
4. In lieu of, or in combination with Subsections 1, 2 and 3 of this Section, when:
 - A. A city owned or privately owned sewage disposal system is not available, or
 - B. Lots are over 2 1/2 acres in size, or

C. An alternate sewer treatment facility has been approved and authorized by the State of Oregon Department of Environmental Quality.

then a statement shall be placed on the face of the final plat or map which states:

A subsurface site evaluation or an alternative sewer treatment facility has been approved and authorized by the State of Oregon Department of Environmental Quality for those lots noted hereon.

In the situation where an alternative sewer treatment facility has been authorized, or an expiration date has been specified relating to Subsection (1), (2) and (4) of this Section, then an appropriate disclosure shall be placed on the face of the final plat or map indicating the location and type of system authorized and/or the date of expiration.

5. In lieu of, or in combination with Subsection 1, 2, 3 and 4 of this Section, when a lot is created for non-residential purposes only, and no city owned or privately owned sewage disposal system, alternate treatment facility or approved septic site will be provided, then a statement shall be placed on the face of the final plat or map which states:

No city owned or privately owned sewage disposal system, alternate treatment facility or approved septic site will be provided to the purchaser of any parcel depicted hereon as NON-RESIDENTIAL.

CHAPTER 8. Major Partitions, Supplementary Provisions.

8.000 Street Improvements

1. Any proposed parcel not adjoining a dedicated public road that requires the creation of a road, street or way for access shall constitute a major partition and shall be subject to the provisions contained in this ordinance.
2. Except as otherwise provided in this Section, major partition maps shall not be granted final approval until the applicable street improvements are completed in accordance with this Ordinance.
3. In lieu of subsection (1) above, a bond may be granted pursuant to Chapter 13 of this Ordinance.

CHAPTER 9. Subdivisions, Supplementary Provisions.

9.000 Street Improvements

1. Except as otherwise provided in this Section, subdivision plats shall not be granted final approval until the applicable street improvements are completed in accordance with this Ordinance.
2. In lieu of subsection (1) above, a bond, cash security, escrow agreement or open letter of credit and performance agreement shall be executed pursuant to Chapter 13 of this Ordinance.


9.010 Subdivision of Agricultural and Forest Lands - It is the intent of Yamhill County to concentrate the major portion of its population within the rural development and urbanizable areas. It is also the intent of the County to preserve, wherever possible, the productive timber and agricultural lands of the County and to ensure that the rural character of an area is not compromised by overdevelopment resulting in excessive traffic, polluted soil and water supplies, or land use conflicts between farm and nonfarm interests, resulting in the costly extension of public services. Therefore, the creation of four or more lots within one calendar year shall not be permitted in the F-40, ^{or AF-20} EF-40 Zones as indicated on the Official Zoning Map of Yamhill County.

9.020 Park Requirements - All Land Divisions - The Director, the Commission or Hearings Officer shall require a fee, to be determined by order of the Board, for each parcel created by land division to be paid into the Yamhill County Park Trust Fund upon submission of the final map or plat to the Planning Department.

1. Expenditure of funds. All funds received shall be credited to a park acquisition, development and maintenance trust fund and shall be deposited with the County Treasurer for the purpose of acquiring, or developing suitable sites for parks or for maintaining or further developing existing parks. Such funds shall be expended only on order of the Board for the purposes of acquiring, developing or maintaining lands for park and recreational uses, and then only for such lands as the Board shall approve as suitable and adaptable for such purpose and in the area impacted by the development.
2. No proposed Land Division shall receive final map or plat approval until the park fee has been assessed and paid in accordance with this ordinance.

ARTICLE IV
FINAL PROCEDURE

**FINAL PROCEDURE
MINOR AND MAJOR PARTITIONS**



CHAPTER 10. Final Application and Review Procedures for Major and
Minor Partitions.

10.000 Application for Final Partition Map Approval - An application for a partition final map approval shall be submitted to the Director by the owner(s) upon satisfactory completion and approval of the preliminary map. The application shall be made no later than six (6) months after the date on which the partition preliminary plan was approved as required by Section 4.090 of this Ordinance. No final partition map may be submitted for consideration and approval unless a preliminary map for the described area has previously been submitted and approved by the County as provided in this Ordinance.

1. A final minor/major partition map application shall include the following:

A. An exact reproducible original transparency of the final partition map and four copies thereof. The map must show all parcels being created and shall be drawn in the following manner:

(1) The map shall be clearly and legibly drawn in a manner which may be microfilmed without loss of detail.

(2) The drafting material, lettering and drawing shall have characteristics of adequate strength and permanence, as well as suitability for binding and copying as specified by the County Surveyor.

(3) The final map size shall be 18 inches by 24 inches. The County Surveyor may establish the format to use for final maps. In cases of

large lots or when necessary, two or more sheets may be utilized subject to approval by the County Surveyor.

B. The final map shall contain the following:

- (1) Signature of all persons having any vested right, title or interest in the subject property or their authorized representative.
- (2) North point, scale and date submitted. The final map shall be drawn to a scale of 1" = 100'. Deviations of the scale may be approved by the County Surveyor and the Director.
- (3) A sufficient description to define the location and boundaries of the map area. Together with dimensions in feet and hundredths of feet. Together with dimensions and parcel size in area by square feet or acreage.
- (4) The location and dimensions of all existing and proposed public or private roads and names as appropriate.
- (5) A designation of all areas being reserved for common use and the conditions being imposed thereon (may be referenced by volume and page from the County Deed and Mortgage Records).
- (6) A designation, purpose, location and dimension of all existing, approved or proposed access or utility easements.

- (7) A designation of all areas covered by water and the location, width and direction of flow of all water courses.
 - (8) A designation of the 100 year flood elevation as determined in accordance with the County Flood Hazard Ordinance.
 - (9) A designation of any area being dedicated by the owner, including its purpose and a legally effective written dedication thereof.
 - (10) A designation of any special notice, requirement or restriction required by the County as a condition of approval.
- C. A copy of the covenant or deed restrictions (if any) that will be placed on the partitioned land.
 - D. A copy of all documents relating to the establishment and maintenance of private facilities, common areas and easements.
 - E. A copy of all documents relating to additional requirements or restrictions required by the County as a condition of approval.
 - F. The appropriate fees as established pursuant to Chapter 17 of this Ordinance.
2. A final minor partition map application creating parcels which are ten acres or less in area and all major partition applications shall include, in addition to the provisions of Section 10.000(1), the following:

- A. The description, location, material and approximate size of monuments. Monuments shall meet the specifications of the office of the County Surveyor and shall not be less than those required by the State of Oregon and this Ordinance.
- B. The affidavit of the Surveyor who did the map and survey work.
- C. Tentative survey of the proposed road boundary/ improvements.
- D. Centerline survey of the proposed road(s), legal descriptions and a dedication deed if required. A bond and performance agreement may be submitted in accordance with the provisions of Article V, Chapter 13.

10.010 Director Review-Final Major or Minor Partition Application -

Upon receiving the final partition application, the Director shall determine if the application conforms to the preliminary map, conditions of approval and the requirements of this Ordinance. The Director shall not approve the final partition application and shall return such application to the partitioner at any time during the final review procedure if it is found to be deficient in meeting the requirements of this Ordinance, the preliminary map or conditions of approval. If no deficiencies are found, the Director shall deliver the map and all pertinent data to the County Engineer for review.

10.020 County Engineer - Final Review of Major Partition - The County Engineer shall review the major or minor partition map and accompanying material to ensure that:

1. All improvements or requirements as specified by this Ordinance and the requirements of the Standards and Specifications for Road Construction In Yamhill County, Oregon, have been completed and approved, or
2. A performance agreement or improvement agreement has been submitted to the County Engineer pursuant to Chapter 13 of this Ordinance and approved by the Yamhill County Board of Commissioners.

The County Engineer shall recommend approval of the major or minor partition map unless he makes a specific finding that the map does not comply to one or more of the above stated requirements.

The Engineer shall sign the final major or minor partition map if no deficiencies are found, and the map and all pertinent data shall be delivered to the County Surveyor for review.

10.030 County Surveyor - Final Review - The County Surveyor shall review the major or minor partition map and accompanying material to ensure the sufficiency of affidavits, the correctness of surveying data, the accuracy of mathematical data and computations, and compliance with the requirements of this Ordinance, and Chapter 92 of the Oregon Revised Statutes (ORS). The County Surveyor shall recommend approval of the major or minor partition map unless he makes a specific finding that the map does not comply to one or more of the above stated requirements.

The County surveyor shall sign the final major or minor partition map if no deficiencies are found, and the map and all pertinent material shall be delivered to the Director.

10.040 Director-Review - The Director shall sign the final major or minor partition map upon verifying that:

1. All signatures necessary for approval of a major or minor partition have been placed on the final partition map, and
2. The final partition application conforms to this Ordinance, the preliminary map and conditions of approval.

Upon the Directors approval and signing of the final partition map, the map and all pertinent material shall be promptly delivered to the County Clerk to be recorded.

10.050 Distribution of Major or Minor Partition Copies - Following the recording of the major or minor partition map, the Director shall furnish and distribute a copy of the map to each of the following:


1. County Surveyor.
2. County Engineer.
3. County Sanitarian.
4. County Assessor.
5. Oregon State Department of Commerce, Real Estate Division, Subdivision Section.

10.060 Expiration of Approval-Major or Minor Partition - The preliminary partition approval shall be null and void and final approval shall not be granted if:

1. After final review by the Director, the partition application does not comply with this Ordinance, the preliminary map or conditions of approval, or
2. The final partition application has not been submitted to the Director in complete form within one (1) year from the date of preliminary approval, or
3. The final partition is not recorded within 90 days from the date the final partition application is submitted to the

Director, because of deficiencies within the final partition application and not from a delay resulting from the processing by the County of the final partition application.

FINAL PROCEDURE SUBDIVISIONS



CHAPTER 11. Final Application and Review Procedure for Subdivisions

11.000 Application for Subdivision Plat Approval - An application for a subdivision plat approval shall be submitted to the Director by the owner. The application shall be made no later than one year after the date on which the subdivision preliminary plat was approved as required by Section 4.090 of this Ordinance. No subdivision plat may be submitted for consideration and approval unless a preliminary plat for the described area has previously been submitted and approved by the County as provided in this Ordinance. The application shall contain the following information:

1. A final subdivision plat, surveyed by a land surveyor, registered with the State of Oregon, and an exact reproducible transparency, and four copies thereof.
 - A. The plat shall be clearly and legibly drawn in a manner which may be microfilmed without loss of detail.
 - B. The drafting material, lettering and drawing shall have characteristics of adequate strength and permanency as well as suitability for binding and copying as specified by the County Surveyor.
 - C. The overall size of plats shall be 18 inches by 24 inches and shall include an additional 3 inch binding strip. The County Surveyor may establish the format to use for plats.
 - D. The subdivision plat shall contain the following:
 - (1) Name of Subdivision.
 - (2) Signature of all persons having any vested right, title or interest in the subject property or their authorized representative.

- (3) North point, scale and date submitted.
The final plat shall be drawn to a scale of 1" = 100'. Deviation of the scale requirement may be approved by the County Surveyor.
- (4) A sufficient description to define the location and boundaries of the plat area.
- (5) Block indicators, lot numbers, street names and lot lines within the plat area with dimensions in feet and hundredths of feet. Blocks shall be numbered or lettered consecutively through all additions to a single development.
- (6) The location and dimensions of all existing and proposed public or private roads and names, as appropriate.
- (7) Description and location of all permanent reference monuments.
- (8) A designation, width and location of all existing approved or proposed access or utility easements.
- (9) A designation of all areas being reserved for common use and the conditions being imposed thereon (may be referenced by volume and page of the County Deed Records).
- (10) A designation of all areas covered by water and the location, width and direction of flow of all water courses.
- (11) A designation of the 100 year flood elevation as determined in accordance with the County Flood Hazard Ordinance.

- (12) The location, material and size of monuments. Monuments shall meet the specifications of the office of the County Surveyor and shall not be less than those required by the State of Oregon and this Ordinance.
 - (13) A designation of any area being dedicated by the owner, including its purpose and a legally effective written dedication thereof.
 - (14) A designation of any special notice, requirement, or restriction required by the County as a condition of approval.
 - (15) The affidavit of the surveyor who did the plat and survey work.
2. A copy of the covenants (if any) that will be placed on the subdivision.
 3. A copy of all documents relating to establishment and maintenance of private facilities, common areas and easements.
 4. A copy of all documents relating to additional requirements or restrictions required by the County as a condition of approval.
 5. The appropriate fees as established pursuant to Chapter 17 of this Ordinance.

11.010 Director Review - Final Subdivision Application - Upon receiving the final subdivision application, the Director shall determine if the application conforms to the preliminary plat, conditions of approval and the requirements of this Ordinance. The Director shall not approve the final subdivision application and shall return such application to the subdivider at any time during the final review procedure if it is found

to be deficient in meeting the requirements of this Ordinance, the preliminary plat or conditions of approval. If no deficiencies are found by the Director on the final subdivision application, the plat and all pertinent data shall be delivered to the County Sanitarian for review.

11.020 County Sanitarian - Review - The County Sanitarian shall review the subdivision plat and accompanying material to ensure that:

1. All proposed lots have been approved for sewage disposal in accordance with the standards and specifications as prescribed by the Oregon State Department of Environmental Quality and ORS Chapter 92.
2. A performance agreement or improvement agreement has been submitted to the County Sanitarian pursuant to Chapter 13 of this Ordinance and approved by the Yamhill County Board of Commissioners.

The County Sanitarian shall recommend approval by the County Health Officer of the subdivision plat unless he makes a specific finding that the plat does not comply to one or more of the above stated requirements.

The County Health Officer shall sign the Final Subdivision Plat if no deficiencies are found, and the plat and all pertinent data shall be delivered to the County Engineer for review.

11.030 County Engineer - Review - The County Engineer shall review the subdivision plat and accompanying material to ensure that:

1. All improvements as required by this Ordinance and the requirements of the Standards and Specifications for Road Construction In Yamhill County, Oregon, have been completed and approved, or
2. A performance agreement or improvement agreement has been submitted to the County Engineer pursuant to Chapter 13 of

this Ordinance and approved by the Yamhill County Board of Commissioners.

The County Engineer shall approve the subdivision plat unless he makes a specific finding that the plat does not comply to one or more of the above stated requirements.

The Engineer shall sign the final subdivision plat if no deficiencies are found, and the plat and all pertinent data shall be delivered to the County Surveyor for review.

11.040 County Surveyor - Review - The County Surveyor shall review the subdivision plat and accompanying material to ensure the sufficiency of affidavits, acknowledgments, and dedications, the correctness of surveying data, the accuracy of mathematical data and computations, and compliance with the requirements of this Ordinance, and Chapter 92 of the Oregon Revised Statutes (ORS). The County Surveyor shall approve the subdivision plat unless he makes a specific finding that the plat does not comply to one or more of the above stated requirements. Fees may be charged by the Surveyor's Office pursuant to ORS, Chapter 92.

The County Surveyor will sign the final subdivision plat if no deficiencies are found and the plat and all pertinent data shall be delivered to the County Assessor for review.

11.050 County Assessor - Review - The County Assessor in conjunction with the County Tax Collector shall ensure that taxes, special assessments, fees, or other charges required by law to be placed on the tax roll have been paid in accordance to the requirements of Chapter 92 of the Oregon Revised Statutes (ORS). The County Assessor shall approve the subdivision plat unless he makes a specific finding that the subdivider has not complied with the above mentioned requirement. The County Assessor shall sign the final subdivision plat if no deficiencies are found and the plat and all pertinent data shall be delivered to the Director for review.

11.060 Director-Review - The Director shall sign the final subdivision plat upon verifying that:

1. All signatures necessary for approval of a subdivision (excluding the signatures of the Board) have been placed on the final subdivision plat, and
2. The final subdivision application conforms to this Ordinance, the preliminary plan and conditions of approval.

Upon signing the final subdivision plat by the Director, the plat and all pertinent material shall be delivered to the County Board of Commissioners.

11.070 Board of Commissioner's - Review - If a majority of the Board determines that the plat is in conformity with the requirements of this Ordinance, the plat shall be approved and signed. The Board shall send notice of such action to the applicant and the Director within ten days of such action.

11.080 Delivery of Subdivision to County Clerk - Following the approval by the Board, the plat and all pertinent material shall be promptly delivered to the County Clerk by the Board for recording.

11.090 Distribution of Subdivision Plat Copies - Following the recording of the subdivision plat, the Director shall furnish and distribute a copy of the plat to each of the following:

1. County Surveyor.
2. County Engineer.
3. County Sanitarian.
4. County Assessor.
5. Oregon State Department of Commerce Real Estate Division, Subdivision Section.

11.100 Expiration of Approval-Subdivision - The preliminary subdivision approval shall be null and void and final approval shall not be granted if:

1. After final review by the Director, the subdivision application does not comply with this Ordinance, the preliminary plan and conditions of approval, or
2. The final subdivision application has not been submitted to the Director in complete form within one year from the date of preliminary approval, or
3. The final subdivision plat is not recorded within 90 days from the date the final subdivision application is submitted to the Director, because of deficiencies within the final partition application and not from delays resulting from the processing by the County of the final Subdivision Application.

ARTICLE V
ADMINISTRATION

CHAPTER 12. Administrative Authority

12.000

1. The Director shall have the authority and it shall be obligatory to his office to:
 - A. Act in accordance with and interpret the provisions of this Ordinance in such a manner so as to carry out its purpose and intent. In the event that the Director is for any reasons unable to perform his duties, or that such position should become vacant temporarily, the authority granted herein shall, on a motion of the Board, revert with the Board until such time as the Director is again able to serve, or in the case that a new Director is appointed, the Board by order vests in him such authority.
 - B. Appoint a subordinate staff member(s) to review land partitions and subdivisions for compliance with the requirements of this Ordinance, and to act in behalf of the Director on such matters.
 - C. Require supplementary information which is deemed necessary in order to carry out the intent of this Ordinance and the Comprehensive Plan.
 - D. Require dedication or an agreement to dedicate land and easements for right-of-way purposes and may specify conditions or modifications on the preliminary map or preliminary plat, necessary to meet County standards established in this Ordinance or the County Roadway Standards.
 - E. The naming of all streets or roads shall be subject to Directors approval.

- F. The naming of all Subdivision Plats shall be subject to Director approval.
- G. Grant extension of the time requirements specified within this Ordinance, provided such extension shall not exceed the length of the initial time period.
- H. Schedule the Commission or Hearings Officer to review and hold a public hearing on any matter subject to the requirements of this Ordinance when requested by the owner, or when irreconcilable differences arise between the owner and:
- (1) the Director, or
 - (2) the Planning Advisory Committee, whose district includes the property intended to be subdivided, or
 - (3) one or more property owners whose property lies within 250 feet of the proposed subdivision, or
 - (4) any person who is specially, personally or adversely affected by the application.
 - (a) Upon the request of a hearing by an adjacent property owner or by a person affected by the application, such person shall provide the required fee for such hearing.
 - (b) In all other instances the applicant shall provide the required fee for such hearing.

2. The Land Development Review Committee (LDRC)

shall have the authority to:

- A. Examine all preliminary plats, preliminary maps and applications for compliance to the requirements of this Ordinance, and prepare appropriate written statements with respect to any matter or information deemed necessary for the owner's or public's benefit. All written statements so prepared should be submitted to the Director and owner at least two days prior to any scheduled or anticipated official action on the application. In addition to the preparation of the individual written statements on an application, the members of the LDRC shall also meet as a committee at a regularly scheduled public meeting to consider the application and form a committee recommendation thereon. The Director shall attend every regularly scheduled LDRC meeting. Failure of any or all of the other committee members to attend the meetings shall not invalidate any action subject to this Ordinance.

3. The Chairman of the LDRC (Director) shall have the authority to take action on all matters relating to approval, conditional approval or disapproval of:

- A. Major partitions.
- B. Minor partitions.
- C. Subdivisions, provided all grievances (if any) between owners and those persons, agencies, departments or committees noted in Section 12.000, Subsection 1., paragraph F. of this Ordinance can be reconciled at or prior to the LDRC meeting. When irre-

concilable differences remain at the close of any review of a subdivision application or preliminary plat, then a formal public hearing before the Commission (or Hearings Officer if such is available) shall be held pursuant to Chapter 15 of this Ordinance.

4. The Commission or Hearings Officer, in cases where a public hearing is required or requested pursuant to this Ordinance, shall have the authority to:
 - A. To act in accordance with and interpret the provisions of this Ordinance in such a way as to carry out its purpose and intent.
 - B. Examine all preliminary plats, preliminary maps and applications for compliance to the requirements of this Ordinance, and prepare appropriate written statements with respect to any matter or information deemed necessary for the owner's or public's benefit.
 - C. Take action on all matters relating to the approval, conditional approval or disapproval of major partitions, minor partitions or subdivisions.
 - D. Require supplementary information deemed necessary in order to carry out the intent of the Comprehensive Plan, Zoning Ordinance and this Ordinance.
 - E. Require dedication of land and easements for right-of-way purposes and may specify conditions or modifications on the preliminary plat or preliminary map, necessary to meet minimum county standards established in this Ordinance or the County Roadway Standards.
 - F. Grant extensions of the time requirements specified within this Ordinance, provided an extension shall not exceed the length of the initial time period.

CHAPTER 13. Bonding, Performance Agreements.

13.000

1. Before final approval may be granted on any subdivision plat or major partition map, the owner shall either install the required improvements or shall execute and file with the Yamhill County Clerk an agreement between himself and the Board, specifying the period within which he or his agent or contractor shall complete all improvements required by this Ordinance, and/or any Board Orders relative to the administration of this Ordinance, and providing that if he shall fail to complete the work within the specified period, the County may complete the same and recover the full cost and expense thereof from the owner. The agreement shall also provide for reimbursement to the County by the owner for costs incurred by the County for engineering and inspection of any required improvements and incidental expenses related thereto, and for the cost of replacement and repair of any existing public improvements damaged by the owner in the development of the subdivision or partition. The agreement may also provide for the construction of the improvements in units or phases, for an extension of time under conditions therein specified, and for the termination of the agreement upon the completion.
2. The owner shall file with the agreement to ensure his full and faithful performance thereof, one of the following:
 - A. A surety bond executed by a surety company authorized to transact business in the State of Oregon and on a form and with covenants and stipulations approved by the Board;

- B. Cash or certified check; or
 - C. An escrow agreement between the owner and a bank or trust company authorized to transact business in the State of Oregon, and on a form and with covenants and stipulations approved by the Board.
 - D. An open letter of credit from a financial institution authorized to transact business in the State of Oregon, and on a form and with covenants and stipulations approved by the Board.
3. The assurance of full and faithful performance shall be for a sum approved by the Board on the recommendation of the Engineer, sufficient to cover the cost of the improvements, engineering, inspection and incidental expenses, replacement and repair of existing roads and other public or private improvements damaged in the development of the subdivision or partition, and a reasonable estimate of increased costs due to inflation for those projects to take place over a period of one or more years.
4. In the event the applicant or developer fails to complete all improvement work required in accord with this Ordinance, and the County has to complete same, or if the owner fails to reimburse the County for the cost of engineering, inspection and incidental expenses, or to cover the cost of replacement and repair of existing roads or other improvement damages in the development of the subdivision or partition, the Board shall call on the surety or trustee for reimbursement, or shall appropriate from any cash deposit funds or escrow accounts for reimbursement. In any such case, if the amount of surety bond, deposit in escrow, or cash deposit exceeds all

costs and expenses incurred by the County, the Board shall release the remainder of the bond or cash deposit, and if the amount of the surety bond, deposit in escrow, or cash deposit is less than the costs and expenses incurred by the County, the owner shall be liable to the County for the deficiency.

5. The agreement between the Owner and Yamhill County shall be on a form approved by the County.

CHAPTER 14. Variances.

14.000

1. Application - Variance procedure as defined in this Chapter shall apply to:

- A. Major Partitions.
- B. Minor Partitions.
- C. Subdivisions.
- D. Roads in conjunction with a partition or subdivision.

Variances to road requirements not specified within this Ordinance shall be governed by the variance procedure defined in the County Road Standards.

2. Procedures - A petition for any such variance shall be submitted in writing by the owner at the time when the preliminary plat or preliminary map is filed for the consideration of the Director. The petition shall state fully the grounds for the application and all of the facts relied upon by the petitioner.

3. General - Where the Director, Commission or Hearings Officer finds that extraordinary hardships or practical difficulties may result from strict compliance with these regulations and/or the purposes of these regulations may be served to a greater extent by an alternative proposal, it may approve variances to these Land Division regulations so that substantial justice may be done and the public interest secured, provided that such variance shall not have the effect of nullifying the intent and purpose of this Ordinance; and further provided the Commission or Hearings Officer shall not approve variances unless it shall make findings based upon the evidence presented to it in each specific case that:

- A. The granting of the variance will not be detrimental to the public safety, health, or welfare or injurious to other property;
 - B. The conditions upon which the request for a variance is based are unique to the property for which the variance is sought and are not applicable generally to other property;
 - C. Because of the particular physical surroundings, shape or topographical conditions of the specific property involved, a particular hardship to the owner would result, as distinguished from a mere inconvenience, if the strict letter of this Ordinance is carried out;
 - D. The variances will not in any manner vary the provisions of the Comprehensive Plan, Zoning Ordinance, or any other ordinances legally adopted or amended.
4. Conditions - In approving variances, the Commission or Hearings Officer may require such conditions as will, in its judgment, secure substantially the objectives of the standards or requirements of this Ordinance.

CHAPTER 15. Public Hearings.

15.000 Public Hearings Required - A public hearing before the Commission (or Hearing Officer if such is available) may be held on all variance requests subject to the provisions of this Ordinance when requested by the Director or a person pursuant to Section 12.000, Subsection 1, paragraph F of this Ordinance. Public hearings shall be governed by the Rules of Procedure for the Conduct of Hearing Related to Land Use Matters adopted March 12, 1974 by the Yamhill County Board of Commissioners, as may be amended.

15.010 Notice of a Public Hearing - At least thirty (30) days prior to the hearing, notice of the hearing shall be sent by mail to the owner, Planning Advisory Committee whose district includes the property intended to be subdivided or partitioned, and all property owners within 250 feet of the property which is the subject of the application, in addition the subject property shall be posted in a conspicuous manner along all public road accesses. Notice shall also be given by publication in a newspaper of general circulation in the area of the subject property at least twenty (20) days prior to the hearing.

15.020 Continuation of Public Hearing - A public hearing before the Commission or Hearing Officer may be continued and renotification need not be made provided the matter is continued to a time certain.

CHAPTER 16. Appeals

16.000 Appeals of the Director, Commission or Hearing Officer

1. Where it is alleged that there is error in any order, requirement, decision or determination made by the reviewing body, an appeal therefrom may be made by an affected party only to the Board on a form prescribed by the Director. Such appeal shall be made within fifteen (15) days of the decision on the proposed action. Such written appeal shall be filed with the Director and shall be accompanied by the appropriate filing fee as contained in Chapter 17 of this Ordinance. The Board, on its own motion may order review of any formal decision made at a public hearing or by the Director pursuant to this Ordinance, within thirty (30) days of the decision.
 - A. The Board shall review the decision of the Director, Commission, or Hearings Officer for procedural defect(s) or incorrect interpretation of officially adopted plans, ordinances, resolutions, rules, regulations and official policies (if written).
 - B. The Board shall not find in favor of the applicant when the result would otherwise have required a variance, zone amendment or other more applicable application unless the procedure is followed for a variance, zone amendment or other more applicable application.
2. Unless otherwise provided by the Board, the review of the decision of the reviewing body shall be confined to the record of the proceeding, which shall include:

- A. All materials, pleadings, memoranda, stipulations and motions submitted by any party to the proceeding and received or considered by the Director, Commission or Hearings Officer as evidence.
 - B. All materials submitted by the Director with respect to the application.
 - C. The transcript (i.e., mechanical or written) of the public hearing of the Commission or Hearings Officer if a public hearing was held.
 - D. The findings and action of the Director, Commission or Hearings Officer and the notice of review from the appellant.
 - E. Argument by the parties or their legal representatives at the time of review before the Board, such argument shall not be considered as evidence in the matter.
3. The Board upon its own motion or upon the motion by a party may elect to hear the application de novo or allow testimony and other evidence in addition to that already on the record.
4. The Board may admit additional testimony and other evidence without holding a de novo hearing if it is satisfied that the testimony or other evidence could not have been presented upon initial hearing and action. In deciding such admission, the Board shall make findings which consider the following:
- A. Prejudice to parties.
 - B. Convenience of locating the evidence at the time of initial hearing.
 - C. Surprise to opposing parties.

- D. Time when notice was given to other parties as to the attempt to admit additional testimony or evidence.
 - E. The competency, relevancy and materiality of the proposed testimony or other evidence.
5. In hearing and deciding an appeal, the Board may modify, reverse or affirm all or part of the order, requirement, decision, or determination of the reviewing body, or may remand the matter back to the reviewing body for additional information. For all cases the Board shall make findings based on the record before it and any testimony or other evidence received by it as justification for its action.

16.010 Stay of Preliminary Approval - The filing of any appeal from, or any review of any decision of the Director, Commission or Hearings Officer pursuant to the provisions of this Ordinance shall stay preliminary approval, if any, of the matter under appeal or review until a final decision is made by the Board on such appeal or review, and until the appeal period has expired for judicial or administrative review of that final decision. Any review or appeal from the final decision of the Board shall also stay the effect of preliminary approval, if any, until the final resolution of such appeal or review is made.

CHAPTER 17 Filing Fees

17.000 Fees shall be collected by the Director in the amounts established by order of the Board of Commissioners for the following purposes:

1. Land Division Applications.
 - A. Minor Partitions - Preliminary and Final Application.
 - B. Major Partitions - Preliminary and Final Application.
 - C. Subdivisions - Preliminary and Final Application.
 - D. Variances.
 - E. Appeals (Notice of Review).
2. Park and Recreation Assessment.
 - A. Single Family residential parcel.
 - (1) An additional fee may be assessed if additional dwelling units are placed upon a parcel by permitted uses, conditional uses or temporary structure permits.
 - B. Multi-family residential parcels.
3. At or before the time of filing a subdivision plat or partition map, the applicant shall pay the County Surveyor and/or County Clerk fees pursuant to ORS 92 and the County fee schedule.

ARTICLE VI
GENERAL PROVISIONS

CHAPTER 18. General Provisions.

18.000 Authorization - Authorization for this Ordinance is contained in the Oregon Revised Statutes, Chapter 92, Sections 92.010 to 92.990 inclusive, entitled "Plats and Subdivisions"; Chapter 197, Sections 197.005 to 197.795 inclusive, entitled "Comprehensive Planning Coordination; Planning Districts"; and Chapter 215, Sections 215.010 to 215.170 inclusive entitled "County Planning".

18.010 Jurisdiction -

1. This Ordinance shall apply to all divisions of land as defined herein, located within the unincorporated area of Yamhill County, Oregon.
2. No land shall be subdivided or partitioned within the unincorporated area of Yamhill County except as provided within this Ordinance.
3. No building permit or certificate of occupancy shall be issued for any lot which was created by subdivision or partition after the effective date of, and not in conformity with the provisions of this Ordinance, and no excavation of land or construction within any proposed partition or subdivision of any public or private improvements shall take place or be commenced except in conformity with this Ordinance.
4. No road may be constructed within any proposed partition or subdivision except as provided in this Ordinance and the County Road Standards.

18.020 Enactment - In order that land may be subdivided or partitioned in accordance with these purposes and policies, this Ordinance is hereby adopted.

18.030 Interpretation, Conflict and Separability -

1. In their interpretation and application, the provisions of this Ordinance shall be held to be the minimum requirements for the promotion of the public health, safety and general welfare.
2. Conflict with Public and Private Provisions.
 - A. Public Provisions. The regulations are not intended to interfere with, abrogate, or annul any other ordinance, rule or regulation, statute, or other provision of law. Where any provision of this Ordinance imposes restriction different from those imposed by any other provision of this Ordinance or any other ordinance, rule or regulation, or other provision of law, whichever provisions are more restrictive or impose higher standards shall control.
 - B. Private Provisions. This Ordinance is not intended to abrogate any easement, covenant or any other private agreement or restriction, provided that where the provisions of this Ordinance is more restrictive or impose higher standards or regulations than such easement, covenant, or other private agreement or restriction, the requirements of this Ordinance shall govern. Where the provisions of the easement, covenant, or private agreement or restriction impose duties and obligations more restrictive, or higher standards than the requirement of this Ordinance, or the determinations of the County

in approving a subdivision or in enforcing this Ordinance and such private provisions are not inconsistent with this Ordinance or determinations thereunder, then such private provisions shall be operative and supplemental to this Ordinance and determinations made thereunder.

3. Severability. If any part or provision of this Ordinance or application thereof to any person or circumstances is adjudged invalid by any court of competent jurisdiction, such judgment shall be confined in its operation to the part, provision, or application directly involved in such controversy in which judgment shall have been rendered and shall not affect or impair the validity of the remainder of this Ordinance or the application thereof to other persons or circumstances. The County hereby declares that it would have enacted the remainder of this Ordinance even without any such part, provision or application.

18.040 Saving Provision - This Ordinance shall not be construed as abating any action now pending under, or by virtue of, prior existing subdivision regulations, or as discontinuing, abating, modifying, or altering any penalty accruing or about to accrue, or as affecting the liability of any person, firm, or corporation, or as waiving any right of the municipality under any section or provision existing at the time of adoption of this Ordinance, or as vacating or annulling any rights obtained by any person, firm, or corporation, by lawful action of the County except as shall be expressly provided for in this Ordinance.

18.050 Reservations and Repeals - Upon the adoption of this Ordinance according to law, the Subdivision Regulations of Yamhill County, adopted

April 1, 1959, by the County Court; Amendment Ordinance numbers 49, 55 and 56; and order numbers 74-90 and 74-91 adopted by the Board are hereby repealed, except as to such sections expressly retained herein.

18.060 Conditions - Regulation of the subdivision or partition of land and the attachment of reasonable conditions to land divisions is an exercise of valid police power delegated by the state to Yamhill County. The owner has the duty of compliance with reasonable conditions laid down by the County for design, dedication, improvement and restrictive use of the land so as to conform to the physical and economical development of the County and to the safety and general welfare of the future lot owners in the subdivision or partition and the County at large.

18.070 Amendments - For the purpose of providing the public health, safety and general welfare, the Board may from time to time amend the provisions imposed by this Ordinance. Public hearings on all proposed amendments shall be held by the Commission and the Board in a manner prescribed by law.

18.080 Violations and Penalties -

1. Any violation of the provisions of this Ordinance shall be punishable as provided in ORS 92.990. Provided, however, in the event ORS 92.990 is repealed, a violation of this Ordinance shall be punishable by a fine, not to exceed \$500.
2. Each day of a continuing violation constitutes a separate offense and shall be punishable as provided in ORS Chapter 92.990.
3. The penalties provided in Paragraph 1 and 2 above are in addition to, and not a substitute for, those civil remedies Yamhill County has to enforce this Ordinance.

